

- NE3627RSSV 35-3/4" L x 33" D x 27-7/8" H
- NE4827RSSV 47-3/4" L x 33" D x 27-7/8" H
- NE6027RSSV 59-3/4" L x 33" D x 27-7/8" H
- NE7227RSSV 71-3/4" L x 33" D x 27-7/8" H

Included

- NOTE: Glass warranty only applicable to first point of delivery
- Breeze~E (Type-II) self-contained refrigeration
- (2) Levels of clear glass shelving removable and adjustable on 1" centers
- Compressor air rear intake, front discharge
- Condensate pan (self-contained refrig. only)
- LED top & shelf lights
- NOTE: Overall case height is 47-1/4" (includes below counter)
- One piece formed ABS plastic tub
- One year parts & labor; 5 year compressor warranty
- Warmest average product temperature of 40°F or less




Specify	Standard Features	Additional Options
FRAME EXTERIOR COLOR	<ul style="list-style-type: none"> • Powder coated Silversan Black 	<ul style="list-style-type: none"> • Powder coated (stock/non-stock colors) • Stainless steel
INTERIOR COLOR	<ul style="list-style-type: none"> • Powder coated Silversan Black 	<ul style="list-style-type: none"> • NOTE: Interior color must be FDA & NSF approved • Powder coated (stock colors, specify RAL#) • Stainless steel
BASE SUPPORT	<ul style="list-style-type: none"> • Casters (non-locking) w/ levelers (self-cont.) 	<ul style="list-style-type: none"> • 6"H legs • Shims (remote)
LEFT END GLASS	<ul style="list-style-type: none"> • Glass end 	<ul style="list-style-type: none"> • No end glass w/ synchronized defrost
RIGHT END GLASS	<ul style="list-style-type: none"> • Glass end 	<ul style="list-style-type: none"> • No end glass w/ synchronized defrost
REAR DOORS	<ul style="list-style-type: none"> • None (solid back panel) 	<ul style="list-style-type: none"> • Clear glass rear sliding doors • Reflective glass rear sliding doors
LIGHTS	<ul style="list-style-type: none"> • LED 3500K w/ frosted lens 	<ul style="list-style-type: none"> • LED 3000K w/ frosted lens • LED 4000K w/ frosted lens
ELECTRICAL CONNECTION	<ul style="list-style-type: none"> • 10' Straight blade power cord (self-cont.) 	<ul style="list-style-type: none"> • 10' Locking power cord (self-cont.) • Electrical leads (remote)
REAR VENTED PANEL	<ul style="list-style-type: none"> • None 	<ul style="list-style-type: none"> • NOTE: Unit can intake & discharge from rear w/ optional rear vented panel • Powder coated (stock/non-stock colors) • Stainless steel
REFRIGERATION	<ul style="list-style-type: none"> • Breeze~E (Type-II) self-contained refrigeration (rear access) 	<ul style="list-style-type: none"> • Breeze~E (Type-II) self-contained refrigeration (front access) (see important notes) <p>¹ • Remote w/thermostat, solenoid & TXV (front access)</p> <p>² • Remote w/thermostat, solenoid & TXV (rear access)</p>
MISCELLANEOUS		<ul style="list-style-type: none"> • Rear door lock • Second year parts & labor warranty (excludes compressor)
ACCESSORIES		<ul style="list-style-type: none"> • Clean Sweep® coil cleaner (self-cont.) • Night curtain, retractable, non-locking • Removable clear acrylic security cover, locking



Option Notes: 1 - Read important notes for remote options

2 - Read important notes for remote options

Intended Environment: Type II - Designed to operate in ambient conditions of 80°F and 55% relative humidity unless noted otherwise in system information below.			
Zone	Intended Product To Be Displayed		
1	Packaged refrigerated products-Precilled to Warmest Avg Prod Temp.	Warmest Avg Prod Temp °F	40

PLAN VIEW

	"A"	"B"	"C"	"D"
NE3627RSSV	8 1/2"	16"	8 1/2"	9 1/2"
NE4827RSSV	8 1/2"	28"	8 1/2"	9 1/2"
NE6027RSSV	8 1/2"	18 5/8"	8 1/2" x2	9 1/2"
NE7227RSSV	8 1/2"	22"	8 1/2" x2	9 1/2"

SIDE VIEW

NOTES:

1. 11 3/8" TALL, FULL WIDTH OF CASE OPENING IN CABINET OR COUNTER IS REQUIRED TO PULL OUT REFRIGERATION SYSTEM.
2. BACK OF COUNTER / CABINET MUST BE VENTED PROPERLY FOR ADEQUATE AIRFLOW TO CONDENSER.
3. **REPRESENTS REAR PULLOUT REFRIGERATION. AIR FLOW INTAKE AND EXIT DETAILS ARE REVERSED WITH FRONT PULLOUT REFRIGERATION OPTION.
4. SELF-CONTAINED ACCESS ONLY BY PULLING OUT CONDENSER UNIT.
5. 4" OPEN AREA CLEARANCE REQUIRED FOR AIR FLOW FRONT AND REAR OF CASE.

NOTE: ALL DIMENSIONS APPROXIMATE



ELECTRICAL JUNCTION BOX
(SUPPLIED WITH 6" LEADS OR POWER CORD).



LOCATION OF DRAIN TUBE FOR REMOTE REF.
ONLY (SUPPLIED WITH 3/4" OR 1 1/2" PVC TUBE).



REFRIGERATION LINE CONNECTION.
REMOTE FLOOR SINK & UTILITIES
ACCESS AREA.



SELF-CONTAINED CASE SERVICE ACCESS AREA.



DRY CASE SERVICE ACCESS AREA.

Model Technical Specifications

Model	L"	L1"	L2"	System Circuit Volts	Phs	Freq	Amps ***	Watts	Wires	NEMA Plug	SST	Conv. Rack BTUH	Para. Rack BTUH	Est Wt		
NE3627RSSV	N/A	35.75	7.50	Remote (DX)	Circuit #1	110-120	1	60	1.05	35	2+G	Leads Single	20.00	2635	2440	750
				Self-Contained (R290)	Circuit #1	110-120	1	60	15.15	1,502	2+G	5-20P or L5-20P	N/A	N/A	N/A	850
NE4827RSSV	N/A	47.75	7.50	Remote (DX)	Circuit #1	110-120	1	60	1.56	75	2+G	Leads Single	20.00	3478	3220	900
				Self-Contained (R290)	Circuit #1	110-120	1	60	15.65	1,535	2+G	5-20P or L5-20P	N/A	N/A	N/A	950
NE6027RSSV	N/A	59.75	7.50	Remote (DX)	Circuit #1	110-120	1	60	1.60	83	2+G	Leads Single	20.00	4342	4020	900
				Self-Contained (R290)	Circuit #1	208-240	1	60	16.00	2,795	2+G	6-20P or L6-20P	N/A	N/A	N/A	950
NE7227RSSV	N/A	71.75	7.50	Remote (DX)	Circuit #1	110-120	1	60	1.64	94	2+G	Leads Single	20.00	5184	4800	950
				Self-Contained (R290)	Circuit #1	208-240	1	60	16.00	2,807	2+G	6-20P or L6-20P	N/A	N/A	N/A	950

*** Does not include electric defrost on freezer models.

Important Notes:

- 1) REMOTE REFRIGERATION NOTE: Condensing unit not included, floor drain required.
- 2) ELECTRICAL NOTE: If GFCI is required, a GFCI breaker MUST be used in lieu of a GFCI receptacle
- 3) Back side of counter must be open or vented the full length of the unit to allow proper ventilation for the refrigeration system.
- 4) A vent in the front of the counter recommended to help dissipate compressor heat .
- 5) Rear Access - Counter must be configured to allow air to be drawn in the rear and discharged out the front.
- 6) Front Access - Counter must be configured to allow air to be drawn in the front and discharged out the rear.
- 7) 19.25" minimum space required beneath counter surface.
- 8) Glass warranty only applicable to first point of delivery.

⚠ WARNING: This product can expose you to chemicals, including Urethane (Ethyl Carbamate), which are known to the State of California to cause cancer and birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov.



In Accordance with
AHRI Std 1200

DOE 2017
Energy Efficiency
Compliant